



Guy Emanuele Jr. Elementary, Union City Safe Routes to Schools Improvement Plan Site Assessment held April 2016

- 1 Mission Blvd / Decoto Rd**
-Install curb extension at western corner of intersection.
-Install School Warning Assembly A in advance of intersection
- 2 Mission Blvd / Decoto Rd**
Install larger pedestrian refuge islands at eastern corner of intersection.
- 3 2nd St / Decoto Rd**
-Install advance stop bar and marking on 2nd St.
-Replace School Zone sign with School Warning Assembly A.
- 4 Santa Clara Ave / 8th St**
-Restripe bike lanes and markings.
-Install additional bike lane markings in advance of merging areas near ends of blocks.
- 5 3rd St, 4th St, H St, Mission Blvd, and Decoto Rd**
Install School Warning Assembly A.
- 6 Decoto Rd / 3rd St**
-Install speed feedback sign on Decoto Rd.
-Install advance stop bar and markings on 3rd St.
- 7 Decoto Rd**
Install fence in median to prevent mid-block crossings.
- 8 Decoto Rd**
Consider relocating AC Transit bus stop north of driveway to reduce conflicts.
- 9 Decoto Rd**
Install high-visibility crosswalk across driveway.
- 10 Loading Zone**
-Install Pull Forward signs.
-Restripe loading zone with white curb striping.
-Extend white loading zone to increase loading capacity.
-Shorten and restripe yellow curb for deliveries at northeastern end of parking lot.
-Remove existing asphalt ramps in accessible parking spaces and install ADA-compliant curb ramps.
-Stripe loading zone lane to encourage drivers to load and unload close to curb.
- 11 4th St / H St / Decoto Rd**
-Install advance stop bar and marking across 4th St and across Decoto Rd.
-Refresh raised pavement markers in rumble strip across Decoto Rd.
- 12 Decoto Rd Bus Loading Zone**
-Study potential conversion of bus only loading zone to parent loading zone.
-Remove portion of existing sidewalk to create additional loading zone and travel lane for through traffic.
-Install Pull Forward Signs.
-Stripe loading zone curb white.
- 13 Decoto Rd south of 7th St**
Install speed feedback sign.
- 14 Mission Blvd**
Fill sidewalk gap.
- 15 Non-Infrastructure Recommendation**
Continue drop-off procedure on Aspen Loop.