

Tom Kitayama Elementary Safe Routes to School Improvement Plan

Site Assessment held April 2016

- 1 Signage Upgrade**
Update all Assembly A signage approaching the school.
- 2 Town Estates Park Crosswalks**
Install truncated domes at curb ramps.
- 3 Kitayama Driveways**
Install truncated domes where driveways at Kitayama Elementary cross the sidewalk.
- 4 Sunsprite Dr Drop-Off Loop**
Restripe curb from yellow to white.
Replace faded No Parking signs along loop.
Install "No Left Turn" signs at driveway exits.
Restripe existing crosswalk at west end as high-visibility.
Install high-visibility crosswalk through drop-off loop..
- 5 Mirabella Dr X-ing Sign**
Trim street tree to improve crossing sign visibility.
- 6 Kitayama Dr**
Consider closing parking lot during drop-off/pick-up.
Restripe curb from yellow to white.
- 7 Kitayama Dr / Winchester Dr Intersection**
Remove non-compliant Assembly D & B signage.
Install high-visibility crosswalk in east leg of intersection.
- 8 Winchester Dr Drop-Off Loop**
Restripe curb from yellow to white.
Replace faded No Parking signs on loop.
- 9 Winchester Dr / Medallion Dr Intersection**
Remove non-compliant yield paddle.

